

Dane techniczne:

Kubatura:	311 m ³
Powierzchnia zabudowy:	120.9 m ²
Powierzchnia całkowita:	185.2 m ²
Powierzchnia netto:	104.28 m ²
Powierzchnia użytkowa:	116.67 m ²
Wymiary domu:	12.33 x 11.65 m
Minimalne wymiary działki:	19.33 x 22.3 m
Wysokość do kalenicy:	6,02 m / 19,75 ft
Powierzchnia dachu:	185.9 m ²
Kąt nachylenia dachu:	30 degrees


Koszty realizacji:

Realizacja stanu surowego otwartego:	36 600
Realizacja stanu surowego zamkniętego:	47 300
Koszt robót wykończeniowych:	36 000
Realizacja domu pod klucz:	83 300

Koszty są podane w cenach netto, należy doliczyć podatek VAT

Materiały:

- External walls - wooden skeleton - thin- layer plaster on OSB
- Ceiling - wooden beams
- Rafter - rafters supported by purlins
- Roof - tile or meatal roofing tile

**CENA PROJEKTU: 970.00 \$**

	Energy-saving package	bezpł.
	Ventilation and fireplace package	90
	Central vacuum package	70
	The electronic version of the project	120
	Solar installation package	70
	Underfloor heating package	80
	Heat pump package	70
	Water jacket package	70
	Boiler for solid fuel package	80
	Air conditioning package	80
	Fencing projects	140
	Septic tanks sealed package	bezpł.

Larch house is a wooden house, which could serve as a summer or year-round house. It has been designed for a comfortable rest and integrating with the surrounding nature. Silhouette building brings to mind the solidity and elegant simplicity. Functional interior with a large living room connects to the garden via a covered terrace. Larch house is also available in mirror version.

ATTENTION !!!

The term of realization of the project is 4 weeks - please take this into consideration when ordering. We apologies for any inconvenience!

Rzuty:



Elewacje:

